



Photo #79: Vertical exterior framing members spaced at approximately 10 to 11 inches apart along west façade sitting on sill beam (Probe #1).



Photo #80: Large beam observed in ceiling soffit spanning east to west. Beam is a acting as a midspan support for floor joists above that span north to south (Probe #2).





Photo #81:10x7 Exterior spandrel beam running north to south 1st floor ceiling level along west exterior wall. (Probe #2)



Photo #82: Ceiling soffit contains a support beam that runs east to west below the spandrel beam. Beam running east to west supports joists above at midspan. This is an atypical configuration that was most likely a modification and not part of the original timber framing design (Probe #2).





Photo #83: Soffit was opened up to further investigate crack. When soffit at this location was opened up it was empty inside and apparently was just there for aesthetic purposes (Probe #3).



Photo #84: Soffit was opened up to further investigate crack. When soffit at this location was opened up it was empty inside and was just apparently there for aesthetic purposes (Probe #3).





Photo #85: Joists above faux soffit are running north to south and are spaced at 18" inches apart. All other floor joists observed in the original structure above the ground level are running perpendicular to these joists (Probe #3). Further investigation required.



Photo #86: Large floor depression adjacent to load bearing wall 1st floor. This area is directly above girder that is failing in the boiler area and being propped up with temporary columns. Staircase to go up to the second floor was originally located somewhere in this room.





Photo #87: Large floor depression adjacent to load bearing wall 1st floor. This area is directly above girder that is failing in the boiler area and being propped up with temporary columns. Staircase to go up to the second floor was originally located somewhere in this room.




Photo #88: Ceiling joist that was never fully scored into a square framing member and still has bark exterior (Probe #4).





Photo #89: Ceiling joist that was never fully scored into a square framing member and still has bark exterior (Probe #4).



Photo #90: Ceiling joist that was never fully scored into a square framing member and still has bark exterior (Probe #4).





Photo #91: Large shrinkage crack that runs entire floor joist (Probe #4).



Photo #92: Interior girder running north to south is splitting along the mortise and tenon joist connections (Probe #4).





Photo #93: Interior girder running north to south is splitting along the mortise and tenon joist connections (Probe #4).



Photo #94: Wall containing girder beam showing signs of deflection. This girder is directly above girder that is failing in the boiler room area and is being propped up with temporary columns (Probe #5).





Photo #95: Interior girder that is showing signs of deflection. Girder is directly above girder that is failing in the boiler room area and is being propped up with temporary columns (Probe #5).



Photo #96: Mortise and tenon connection between a bracing member and interior girder being held in place with a wooden peg. (Probe #5)





Photo #97: Girder beam that runs north to south in wall that use to be the exterior wall of the original structure (Probe #6).



Photo #98: Old exterior wall vertical member that was never scored down into a square (Probe #6).



2nd Floor



Photo #99: Depression in second floor hallway. Most likely due to weight of walls and bathroom added in this area. Further investigation would be required to figure out exact cause.



Photo #100: Floor joists supporting attic above observed at second floor level are oriented east to west. Large hole drilled through girder for pipe penetration (Probe #7).





Photo #101: Floor joists supporting attic above observed at second floor level are oriented east to west. Large hold drilled through girder for pipe penetration (Probe #7).



Photo #102: Past termite damage was observed in floor joist supporting attic level (Probe #7).





Photo #103: New joists running east to west have been installed at higher level than original joists and are resting on a 2x4 wood ledges that have been nailed to girder to support attic floor above. It is unclear why these joists were installed. Most likely to add additional space for piping below showers and toilets in attic. Further investigation required. Original joists left in place and still supporting ceiling below (Probe #8).






Photo #104: New joists running east to west have been installed at higher level than original joists and are resting on a 2x4 wood ledges that have been nailed to girder to support attic floor above. It is unclear why these joists were installed. Further investigation required to figure out why this was done. Original joists left in place and still supporting ceiling below. Multiple joists supporting attic floor above have holes drilled above their neutral axis at the joists ends where shear force is the highest (Probe #8).





Photo #105: New joists running east to west have been installed at higher level than original joists and are resting on a wood ledge 2x4s that have been nailed to girder to support attic floor above (Probe #8).



Photo #106: New joists running east to west have been installed at higher level than original joists and are resting on a wood ledge 2x4s that have been nailed to girder to support attic floor above (Probe #8). (Probe #8)





Photo #107: Water damage adjacent to east exterior wall of addition. Cause unknown, further investigation required.




Photo #108: View facing northeast in roof void between 2nd floor ceiling joists and roof joists in the addition. Roof joists do not align with ceiling joists and are being supported at midspan with blocking that is resting right onto plaster ceiling (Probe #9).





Photo #109: View facing northeast in roof void between 2nd floor ceiling joists and roof joists in the addition. Roof joists do not align with ceiling joists and are being supported at midspan with blocking that is resting right onto plaster ceiling (Probe #9).

Attic



Photo #110: Pipe penetration drilled through girder drilled above its neutral axis. Observed in unfinished attic area, north side of original structure.





Photo #111: Post in attic space has moved out of place. Mortise and tenon joint that was connecting post to girder below has failed allowing member to rotate (Probe #10).





Photo #112: Post in attic space has moved out of place. Mortise and tenon joint that was connecting post to girder below has failed allowing member to rotate (Probe #11).



Photo #113: Post in attic space has moved out of place. Mortise and tenon joint that was connecting post to girder below has failed allowing member to rotate (Probe #11).





Photo #114: Vertical crack that has opened more towards the bottom observed, attic post Unclear why this has occurred. Further investigation required (Probe #12).





Photo #115: Vertical crack that has opened more towards the bottom observed, attic post Unclear why this has occurred. Further investigation required. New wood joists have been installed going east to west bearing on wood ledge that has been nailed into girder. It is unclear why this was done. Further investigation required (Probe #12).




Photo #116: New wood joists have been installed going east to west bearing on wood ledge that has been nailed into girder. It is unclear why this was done. Further investigation required (Probe #12).





Photo #117: Roof support beam observed to be coming apart.









Photo #118: Roof support beam observed to be coming apart.

















2nd Floor (Attic Floor Framing)

